This schedule is copyright © 3v Architectural Hardware Limited 28/10/2020. Copying any portion of it is not permitted.

3v

Door No.	Door Type	Location	Leaf Size	Leaf Thickness	Rw dB	Fire	Set	3v Butt hinge	3v Butt hinge intumescent packs	3v Fig 1 Overhead door closer	3v Fig 6 Overhead door closer	3v Mortice dead lock	3v Mortice sash lock	3v Cubicle mortice dead lock	3v Lockjatch case intumescent pack	3v Double cylinder UNK	3v Escape cylinder UMK	3v Inclusive WC indictor turn and release	3v Cylinder escutcheon	3v Cylinder pull	3v DJA design BT pull handle	3v Push plate	3v DJA design lever handle	3v FDKS disc	3v FDKL disc	3v Unisex disc	3v Shower disc	3v Floor door stop	3v Kick plate T1	3v Master keys	COMMENTS
Ground																														
D-G01-03	D	New door to Stairs 1	926mm x 2040mm	44mm	TBC	FD30s	1	1.5	1.5	1										1	1		2				1	2			
D-G02-01	B1	New door to WC block	926mm x 2020mm	44mm	TBC	FD30s	2	1.5	1.5		1									1	1		2		1	1		2			
D-G05-01	A2	New door to cleaner's cupboard	826mm x 2020mm	44mm	TBC	FD30	3	1.5	1.5			1			1		1		1	1				2				2			
D-G11-X1	X	Replacement door to plant room	approx 800 x 2100	44mm	TBC	FD30s	12	1.5	1.5	1										1	1		2				1	2			
D-G11-X2	X	Replacement double door to plant room	approx 800 x 2100	44mm	TBC	FD30s	5	3.0	3.0	1										2	2		4				2	4			
D-G12-01	D	New door to Stairs 2	926mm x 2040mm	44mm	TBC	FD30s	6	1.5	1.5		1									1	1		2				1	2			
D-G12-02	D	New door to Stairs 2	926mm x 2040mm	44mm	TBC	FD30s	1	1.5	1.5	1										1	1		2				1	2			
D-G13-03	C1	Laminating Facility	926mm x 2040mm	44mm	-	-	7	1.5		1	1				1		1	1	1	1											
D-G15-01	C2	New door to Painters bay	826mm x 2040mm	44mm	-	-	8	1.5		1		1				1		2		1	1						1	2			
First & Mezz																														
D-ES1-X3	X	Replacement door to stairs FF landing	approx 800 x 2100	44mm	TBC	FD30s	1	1.5	1.5	1										1	1		2				1	2			
D-M01-01	D	New door to Mess Room	926mm x 2040mm	44mm	TBC	FD30s	4	1.5	1.5	1		1			1		1		2		1	1		2				1	2			
D-M03-01	A3	New door to Refurbished Kitchen	726mm x 2040mm	44mm	TBC	FD30	4	1.5	1.5	1		1			1		1		2		1	1		2				1	2			
D-M04-X1	EX	Replacement door to kitchen relocated to WC	approx 800 x 2100	existing		TBC	10	1.5		1				1				1			1	1				1		1	2		Specification to be confirmed
D-M05-02	B1	New door to new mezzanine	926mm x 2040mm	44mm	TBC	FD30	12	1.5	1.5	1										1	1		2				1	2			
D-M05-03	A2	New door to Office 3	826mm x 2040mm	44mm	TBC	FD30	11	1.5	1.5	1			1		1		1		2			1	2				1	2			
D-M06-01	C2	New door to Hot Desk Space	950mm x 2040mm door leaf and 854mm height upper fixed panel	44mm	TBC	-	13	1.5		1			1			1		2				1						1	2			
D-M08-01	C1	New door to FM workshop	950mm x 2040mm door leaf. rebated top edge to 279mm height upper fixed panel,	44mm	TBC	-	8	1.5		1		1				1		2		1	1							1	2			
D-M09-01	C1	New door to Electrician's Workshop	950mm x 2040mm door leaf. rebated top edge to 279mm height upper fixed panel,	44mm	TBC	-	8	1.5		1		1				1		2		1	1							1	2			
D-M10-01	A1	New door to Stairs 2	926mm x 2040mm	44mm	TBC	FD30s	12	1.5	1.5	1										1	1		2				1	2			
D-M11-X1	X	Replacing door to hot desk office 1	approx 800 x 2100	existing	TBC	FD30s	11	1.5	1.5	1			1		1		1		2			1	2				1	2			
D-M12-01	A1	New door to Lockers	926mm x 2040mm	44mm	TBC	-	9	1.5		1		1				1		2		1	1						1	2			
Second																														
D-S03-X1	X	Replacement door to hot desk office 2	approx 800 x 2100	44mm	TBC	FD30s	11	1.5	1.5	1			1		1		1		2			1	2				1	2			
Sundries																														
Master Keys		Exact quantity to be confirmed at time of order					MK																						3	Exact quantity to be confirmed at time of order